Kestrel Industrial Supply Ltd

Engineering the backbone of industry

RC 1928374 • TIN 20384756-0001
Plot 14, Block C, Agbara Industrial Estate, Agbara, Ogun State, Nigeria
+234 800 555 0142 • sales@kestrel-industrial.example • www.kestrel-industrial.example

PO DATE	REQUIRED BY
30/10/2026	20/11/2026
PROJECT	**CONTRACT NO.**
Northgate Factory Ph. 2	NGF/CON/2026/P2-014

PURCHASE ORDER

PO-2026-0089

ORDER FROM · SUPPLIER / VENDOR

Meridian Industrial Wholesale Ltd

Chief Sales Directorate — Engr. T. Olatunji
KM 14, Lagos-Ibadan Expressway, Industrial Corridor, Ogun State
+234 802 444 8811 • sales@meridian-wholesale.example
TIN 29019284-0001

DELIVER TO · SITE

Northgate Foods Factory — Phase 2 (Production Hall & Utilities)

Km 18, Lagos–Ibadan Expressway, Mowe, Ogun State
Site contact: Mr. Ifeanyi Eze — +234 800 555 0120

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT COST (₦)	AMOUNT (₦)
1	**Portland-limestone cement CEM II 42.5R** Dangote-grade bulk supply (synthetic spec) 50 kg bags, palletised *Delivery in 4 tranches*	1,200	bags	₦ 8,550.00	₦ 10,260,000.00
2	**High-yield deformed reinforcement bar Y16** BS 4449:2005 Grade B500B 12 m lengths, mill-certified Bundled & tagged by heat number Delivery tolerance ±2% on tonnage; weighbridge tickets supplied with every load	85	tonnes	₦ 943,000.00	₦ 80,155,000.00
3	**Hot-dip galvanised structural I-beam IPE 300** S275JR — EN 10025 12 m lengths; **galvanised to ISO 1461** Mill test certificates supplied *Optional:* primer plus two-coat polyurethane finish available on request	42	pcs	₦ 398,950.00	₦ 16,755,900.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT COST (₦)	AMOUNT (₦)
4	**Armoured power cable 4-core 95 mm² Cu/XLPE/SWA/PVC** 0.6/1 kV — BS 5467 Drum length 250 m; **cut-to-length** on request Supplied on returnable steel drums	1,500	m	₦ 23,300.00	₦ 34,950,000.00
5	**Main LV distribution board, 800 A, TPN, 36-way** Form 2b, IP54 floor-standing Powder-coated 2 mm sheet steel, 800 A copper busbar Incl. neutral & earth bars; type-tested to IEC 61439 Factory-wired with surge protection and metering CT provisions	6	pcs	₦ 1,517,000.00	₦ 9,102,000.00
6	**MCCB 3-pole 250 A, 36 kA** Adjustable thermal-magnetic trip Breaking capacity 36 kA @ 415 V; rotary handle, terminal shrouds & auxiliary contact included	24	pcs	₦ 116,450.00	₦ 2,794,800.00
7	**Centrifugal end-suction pump set, 7.5 kW** 50 m³/h @ 32 m head — cast-iron volute **Set includes:** 3-phase motor, baseplate, coupling guard, flexible couplings *2-year manufacturer warranty*	4	sets	₦ 1,164,400.00	₦ 4,657,600.00
8	**Axial roof ventilation fan 900 mm, 1.1 kW** IP55, 3-phase, backdraught shutter Galvanised housing; 18,500 m³/h	12	pcs	₦ 315,700.00	₦ 3,788,400.00
9	**Three-phase induction motor 15 kW, IE3, 4-pole, B3** Foot-mounted, 400 V / 50 Hz Class F insulation; IP55; with PTC thermistors	6	pcs	₦ 754,400.00	₦ 4,526,400.00
10	**V-belt, pulley & coupling accessory kit** Assorted B-section	30	lots	₦ 31,550.00	₦ 946,500.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT COST (₦)	AMOUNT (₦)
11	**uPVC pressure pipe 110 mm, PN10** 6 m socketed lengths — water supply Solvent-weld or rubber-ring joint; includes 10% fitting allowance	320	lengths	₦ 15,250.00	₦ 4,880,000.00
12	**Cast-iron flanged gate valve DN100, PN16** Resilient-seated, non-rising stem Epoxy-coated body; handwheel operated; PN16 drilled flanges	18	pcs	₦ 79,150.00	₦ 1,424,700.00
13	**Industrial sanitary suite — floor-mounted WC with cistern & wall-hung basin** Vitreous china, white Complete with seat, 15 mm angle valves, flexible connectors & waste fittings **Includes** installation pack	14	sets	₦ 104,950.00	₦ 1,469,300.00
14	**Safety helmet (hard hat), 6-point ratchet** HDPE shell — EN 397 Colour-coded by trade: white / yellow / blue	180	pcs	₦ 3,450.00	₦ 621,000.00
15	**Safety boots, steel toe-cap & midsole, S3** Oil-resistant PU outsole — sizes 39–46 Supplied in a size run agreed with site HSE	180	pairs	₦ 25,850.00	₦ 4,653,000.00
16	**Desktop workstation, Core i7 / 16 GB / 512 GB NVMe, with 24″ monitor** Business-class tower, Windows 11 Pro **Specification:** 12th-gen Core i7, 16 GB DDR4, 512 GB NVMe SSD, 24″ FHD IPS monitor, keyboard & mouse 3-year on-site warranty **Included:** Windows 11 Pro licence, wired keyboard & optical mouse, power cable Pre-imaged with the client's standard software build; asset-tagged on delivery Rated for 24/7 operation up to 35 °C ambient	20	units	₦ 709,300.00	₦ 14,186,000.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT COST (₦)	AMOUNT (₦)
17	**Managed 48-port Gigabit PoE+ switch with 4 × 10G SFP+ uplinks** Layer 3 lite; rack-mount 1U 740 W PoE budget; includes rack ears & console cable Dual hot-swap PSU bays (one fitted); front-to-back airflow Supports 802.1X, LACP, IGMP snooping, VLAN and QoS Includes 4 × SFP+ direct-attach cables, 1 m	4	pcs	₦ 1,016,800.00	₦ 4,067,200.00
18	**Online double-conversion UPS 10 kVA, 3-phase in / 1-phase out** Rack/tower convertible, with 15-min battery bank True online topology; **N+1 parallel-ready**; SNMP card included Battery: 20 × 12 V 9 Ah sealed lead-acid	3	units	₦ 1,927,000.00	₦ 5,781,000.00
19	**LED high-bay light 150 W, IP65** 5000 K, 120 lm/W, 90° optic Aluminium heat-sink body; 5-year warranty	120	pcs	₦ 31,550.00	₦ 3,786,000.00
20	**LED recessed panel 600 × 600 mm, 40 W** 4000 K, UGR<19	200	pcs	₦ 13,800.00	₦ 2,760,000.00
21	**LED emergency exit sign, 3-hour battery backup** Maintained / non-maintained selectable	36	pcs	₦ 12,200.00	₦ 439,200.00
22	**Heavy-gauge PVC conduit 25 mm with standard junction boxes, saddles, bends and couplers (assorted)** BS EN 61386 — 3 m lengths Lengths priced individually; accessories supplied at the ratio 1 : 1	800	lengths	₦ 1,100.00	₦ 880,000.00
23	**13 A twin switched socket outlet, flush-mount, IP20** White, with 2 × USB-A charging ports	260	pcs	₦ 3,200.00	₦ 832,000.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT COST (₦)	AMOUNT (₦)
24	**Fire extinguisher 9 kg ABC dry-powder, with wall bracket** Rated 55A/233B — EN 3-7 Annual service tag included **Includes** 1 × signage plate per unit	40	pcs	₦ 36,100.00	₦ 1,444,000.00
25	**High-visibility reflective vest, class 2** EN ISO 20471 — 120 gsm Zip front, 2 pockets; sizes M–3XL	220	pcs	₦ 3,100.00	₦ 682,000.00
26	**Exterior weatherproof emulsion paint 20 L** Elastomeric, factory grey (RAL 7040) Two-coat system; coverage ≈ 10 m²/L per coat	160	buckets	₦ 38,150.00	₦ 6,104,000.00

DELIVERY INSTRUCTIONS & SUPPLIER PAYMENT TERMS

Deliver to: Northgate Foods Factory, Km 18 Lagos–Ibadan Expressway, Mowe, Ogun State — Gate 2 (heavy goods).

Delivery window: Mon–Fri 08:00–16:00; 24-hour prior notice to the site store.

Payment: within 30 days upon receipt of delivery and verified invoice.

DIRECTIVES & COMMERCIAL NOTES

- **Procurement for:** Northgate Foods factory — Phase 2 (contract **NGF/CON/2026/P2-014**), as per approved material schedule.
- **Prices are unit costs** agreed under the supplier's quotation ref. MIW/Q/2026/883 dated 22/10/2026.
- Partial deliveries are acceptable only with prior written approval; each delivery must carry a delivery note quoting this PO number.
- **Documentation:** mill test certificates (items 2–3), type-test reports (items 5–6) and warranty cards (items 7–9, 16–18) must accompany the goods.

TERMS & WARRANTIES

1. **Supplier payment terms:** payment within 30 days upon receipt of delivery and a verified tax invoice quoting this PO number.
2. **Delivery:** by 20/11/2026 to the site address shown; early or late delivery requires 48-hour prior notice.
3. **Quality & inspection:** goods are subject to inspection on arrival. Non-conforming goods will be rejected at the supplier's cost and replaced within 7 days.
4. **Penalties:** late delivery attracts 0.5% of the line value per day, capped at 10% of the order value.

Procurement subtotal	₦ 221,946,000.00
PO discount (3.0%)	− 6,658,380.00
Net subtotal	₦ 215,287,620.00
VAT (7.5%)	₦ 16,146,571.50
Inbound freight to site	₦ 650,000.00
Loading & insurance in transit	₦ 185,000.00
Total Order Amount	**₦ 232,269,191.50**

TOTAL AMOUNT IN WORDS

Two Hundred and Thirty-Two Million, Two Hundred and Sixty-Nine Thousand, One Hundred and Ninety-One Naira and Fifty Kobo Only

AUTHORISATION & LEGAL ENDORSEMENT

PURCHASING OFFICER / REQUISITIONER



OFFICIAL STAMP

Mr. Chukwuemeka Daniels — Purchasing Officer (Kestrel Industrial Supply Ltd) • Date: _____

MANAGEMENT / FINANCE AUTHORISATION

Handwritten signature — sign inside this boundary

Authorised by (name): _____ Designation: _____ Date: _____