Kestrel Industrial Supply Ltd

Engineering the backbone of industry

RC 1928374 • TIN 20384756-0001
Plot 14, Block C, Agbara Industrial Estate, Agbara, Ogun State, Nigeria
+234 800 555 0142 • sales@kestrel-industrial.example • www.kestrel-industrial.example

QUOTATION DATE	VALID UNTIL
30/10/2026	13/11/2026
PAYMENT TERMS	**CLIENT RFQ REF.**
70% advance / 30% on completion	NGF-RFQ-2026-118

QUOTATION

QUOT-2026-0045

BILL TO · CLIENT

Northgate Foods Processing Nigeria Ltd

Ms. Adaeze Obi — Procurement Lead
Km 18, Lagos–Ibadan Expressway, Mowe, Ogun State, Nigeria
+234 800 555 0177 • procurement@northgate-foods.example
TIN 31827465-0001

PROJECT INFORMATION

Northgate Foods Factory — Phase 2 (Production Hall & Utilities)

Site: Km 18, Lagos–Ibadan Expressway, Mowe, Ogun State
Contract No.: NGF/CON/2026/P2-014

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT PRICE (₦)	AMOUNT (₦)
1	**Portland-limestone cement CEM II 42.5R** Dangote-grade bulk supply (synthetic spec) 50 kg bags, palletised *Delivery in 4 tranches*	1,200	bags	₦ 10,400.00	₦ 12,480,000.00
2	**High-yield deformed reinforcement bar Y16** BS 4449:2005 Grade B500B 12 m lengths, mill-certified Bundled & tagged by heat number Delivery tolerance ±2% on tonnage; weighbridge tickets supplied with every load	85	tonnes	₦ 1,150,000.00	₦ 97,750,000.00
3	**Hot-dip galvanised structural I-beam IPE 300** S275JR — EN 10025 12 m lengths; **galvanised to ISO 1461** Mill test certificates supplied *Optional:* primer plus two-coat polyurethane finish available on request	42	pcs	₦ 486,500.00	₦ 20,433,000.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT PRICE (₦)	AMOUNT (₦)
GROUP	**ELECTRICAL — POWER CABLES & DISTRIBUTION**				Group Subtotal: ₦ 57,108,000.00
4	**Armoured power cable 4-core 95 mm² Cu/XLPE/SWA/PVC** 0.6/1 kV — BS 5467 Drum length 250 m; **cut-to-length** on request Supplied on returnable steel drums	1,500	m	₦ 28,400.00	₦ 42,600,000.00
5	**Main LV distribution board, 800 A, TPN, 36-way** Form 2b, IP54 floor-standing Powder-coated 2 mm sheet steel, 800 A copper busbar Incl. neutral & earth bars; type-tested to IEC 61439 Factory-wired with surge protection and metering CT provisions	6	pcs	₦ 1,850,000.00	₦ 11,100,000.00
6	**MCCB 3-pole 250 A, 36 kA** Adjustable thermal-magnetic trip Breaking capacity 36 kA @ 415 V; rotary handle, terminal shrouds & auxiliary contact included	24	pcs	₦ 142,000.00	₦ 3,408,000.00
7	**Centrifugal end-suction pump set, 7.5 kW** 50 m³/h @ 32 m head — cast-iron volute **Set includes:** 3-phase motor, baseplate, coupling guard, flexible couplings *2-year manufacturer warranty*	4	sets	₦ 1,420,000.00	₦ 5,680,000.00
8	**Axial roof ventilation fan 900 mm, 1.1 kW** IP55, 3-phase, backdraught shutter Galvanised housing; 18,500 m³/h	12	pcs	₦ 385,000.00	₦ 4,620,000.00
9	**Three-phase induction motor 15 kW, IE3, 4-pole, B3** Foot-mounted, 400 V / 50 Hz Class F insulation; IP55; with PTC thermistors	6	pcs	₦ 920,000.00	₦ 5,520,000.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT PRICE (₦)	AMOUNT (₦)
10	**V-belt, pulley & coupling accessory kit** Assorted B-section	30	lots	₦ 38,500.00	₦ 1,155,000.00
	GROUP PLUMBING & SANITARY MATERIALS			Group Subtotal:	₦ 9,481,000.00
11	**uPVC pressure pipe 110 mm, PN10** 6 m socketed lengths — water supply Solvent-weld or rubber-ring joint; includes 10% fitting allowance	320	lengths	₦ 18,600.00	₦ 5,952,000.00
12	**Cast-iron flanged gate valve DN100, PN16** Resilient-seated, non-rising stem Epoxy-coated body; handwheel operated; PN16 drilled flanges	18	pcs	₦ 96,500.00	₦ 1,737,000.00
13	**Industrial sanitary suite — floor-mounted WC with cistern & wall-hung basin** Vitreous china, white Complete with seat, 15 mm angle valves, flexible connectors & waste fittings **Includes** installation pack	14	sets	₦ 128,000.00	₦ 1,792,000.00
14	**Safety helmet (hard hat), 6-point ratchet** HDPE shell — EN 397 Colour-coded by trade: white / yellow / blue	180	pcs	₦ 4,200.00	₦ 756,000.00
15	**Safety boots, steel toe-cap & midsole, S3** Oil-resistant PU outsole — sizes 39–46 Supplied in a size run agreed with site HSE	180	pairs	₦ 31,500.00	₦ 5,670,000.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT PRICE (₦)	AMOUNT (₦)
GROUP	**COMPUTERS & IT EQUIPMENT**				Group Subtotal: ₦ 22,260,000.00
16	**Desktop workstation, Core i7 / 16 GB / 512 GB NVMe, with 24″ monitor** Business-class tower, Windows 11 Pro **Specification:** 12th-gen Core i7, 16 GB DDR4, 512 GB NVMe SSD, 24″ FHD IPS monitor, keyboard & mouse 3-year on-site warranty **Included:** Windows 11 Pro licence, wired keyboard & optical mouse, power cable Pre-imaged with the client's standard software build; asset-tagged on delivery Rated for 24/7 operation up to 35 °C ambient	20	units	₦ 865,000.00	₦ 17,300,000.00
17	**Managed 48-port Gigabit PoE+ switch with 4 × 10G SFP+ uplinks** Layer 3 lite; rack-mount 1U 740 W PoE budget; includes rack ears & console cable Dual hot-swap PSU bays (one fitted); front-to-back airflow Supports 802.1X, LACP, IGMP snooping, VLAN and QoS Includes 4 × SFP+ direct-attach cables, 1 m	4	pcs	₦ 1,240,000.00	₦ 4,960,000.00
GROUP	**ELECTRICAL — POWER SYSTEMS & LIGHTING**				Group Subtotal: ₦ 17,660,400.00
18	**Online double-conversion UPS 10 kVA, 3-phase in / 1-phase out** Rack/tower convertible, with 15-min battery bank True online topology; **N+1 parallel-ready**; SNMP card included Battery: 20 × 12 V 9 Ah sealed lead-acid	3	units	₦ 2,350,000.00	₦ 7,050,000.00
19	**LED high-bay light 150 W, IP65** 5000 K, 120 lm/W, 90° optic Aluminium heat-sink body; 5-year warranty	120	pcs	₦ 38,500.00	₦ 4,620,000.00
20	**LED recessed panel 600 × 600 mm, 40 W** 4000 K, UGR<19	200	pcs	₦ 16,800.00	₦ 3,360,000.00

#	TECHNICAL SPECIFICATION & BILL OF MATERIALS	QTY	UNIT	UNIT PRICE (₦)	AMOUNT (₦)
21	**LED emergency exit sign, 3-hour battery backup** Maintained / non-maintained selectable	36	pcs	₦ 14,900.00	₦ 536,400.00
22	**Heavy-gauge PVC conduit 25 mm with standard junction boxes, saddles, bends and couplers (assorted)** BS EN 61386 — 3 m lengths Lengths priced individually; accessories supplied at the ratio 1 : 1	800	lengths	₦ 1,350.00	₦ 1,080,000.00
23	**13 A twin switched socket outlet, flush-mount, IP20** White, with 2 × USB-A charging ports	260	pcs	₦ 3,900.00	₦ 1,014,000.00
GROUP	**SAFETY EQUIPMENT & PPE**			Group Subtotal:	₦ 2,596,000.00
24	**Fire extinguisher 9 kg ABC dry-powder, with wall bracket** Rated 55A/233B — EN 3-7 Annual service tag included **Includes** 1 × signage plate per unit	40	pcs	₦ 44,000.00	₦ 1,760,000.00
25	**High-visibility reflective vest, class 2** EN ISO 20471 — 120 gsm Zip front, 2 pockets; sizes M–3XL	220	pcs	₦ 3,800.00	₦ 836,000.00
26	**Exterior weatherproof emulsion paint 20 L** Elastomeric, factory grey (RAL 7040) Two-coat system; coverage ≈ 10 m²/L per coat	160	buckets	₦ 46,500.00	₦ 7,440,000.00

PAYMENT DETAILS (ADVANCE DEPOSIT)

First Meridian Bank (illustrative)
0123456789

Account Name: **Kestrel Industrial Supply Ltd** • Advance payment deposit — 70% of total on acceptance

DIRECTIVES & COMMERCIAL NOTES

- **Scope of supply:** materials, equipment and supplies for **Phase 2** of the Northgate Foods factory (production hall & utilities) under contract **NGF/CON/2026/P2-014**.
- Quantities are based on the bill of quantities issued 12/10/2026 (rev. B); variations will be re-priced at the rates shown.
- **Exclusions:** civil works for plant plinths, permits, third-party testing and any works not itemised above.
- Installation is quoted at the item rates indicated; commissioning is available as a separate line on request.

TERMS & WARRANTIES

1. **Validity:** this quotation is valid for 14 days from the quotation date. Prices are subject to review thereafter due to exchange-rate and commodity movements.
2. **Payment schedule:** 70% advance on order confirmation, 30% on completion of delivery; installation as agreed per milestone.
3. **Delivery:** 4–6 weeks from receipt of advance payment, subject to stock at time of order.
4. **Acceptance:** the quotation becomes binding only when signed and returned with the advance payment or a valid purchase order.

Gross subtotal	₦ 270,609,400.00
Installation / labour	₦ 7,600,960.00
Subtotal discount (2.5%)	− 6,765,235.00
Net subtotal	₦ 271,445,125.00
VAT (7.5%)	₦ 20,358,384.38
Transportation & logistics	₦ 1,850,000.00
Offloading & handling	₦ 420,000.00
WHT (5.0%) — estimated	− 13,572,256.25
Total Quoted Amount	**₦ 280,501,253.13**

TOTAL AMOUNT IN WORDS
Two Hundred and Eighty Million, Five Hundred and One Thousand, Two Hundred and Fifty-Three Naira and Thirteen Kobo Only

AUTHORISATION & LEGAL ENDORSEMENT

PREPARED BY / SALES REPRESENTATIVE



OFFICIAL STAMP

Mr. Chukwuemeka Daniels — Sales Representative (Kestrel Industrial Supply Ltd) • Date: _____

ACCEPTED & APPROVED BY CLIENT

Handwritten signature — sign inside this boundary

Accepted by (name): _____ Designation: _____ Date: _____